

GOVERNMENT OF TELANGANA
ABSTRACT

RWS&S – Telangana Drinking Water Supply Project (Mission Bhagiratha) – Balance Intra Village Works - Entrustment of OHSRs packages – Revision of payment breakup of OHSRs – Amendment - Orders – Issued.

PANCHAYAT RAJ AND RURAL DEVELOPMENT (RWS.IV) DEPARTMENT

G.O.Rt.No.111

Dated: 10.02.2018.

Read the following:

1. G.O.Rt.No.989, PR&RD (RWS.IV) Department, Dated: 08.12.2016.
2. The ENC, RWS&S, Hyderabad, Lr.No.AEE II/DEE/TDWSP (Plg)/Intra Village/2017, dated: 09.9.2017.

ORDER:

In the reference 1st read above, orders were issued prescribing the procedure for entrustment and methodology for execution of Intra Village works of Mission Bhagiratha only.

2. In the reference 2nd read above, the Engineer-in-Chief, Rural Water Supply & Sanitation, Hyderabad has stated that the intra village OHSRs packages are in the process of entrustment to empanelled contractors. While entrustment, majority of the contractors are requesting to revise the payment break up of Intra Village OHSRs as per the payment break up adopted earlier for OHSRs in NRDWP works to increase cash-flow to enable them complete OHSRs without any tribulations.

3. He has also stated that the Chief Engineers Committee discussed the issues elaborately on 18.5.2017 and opined that the payment schedule of OHSRs implemented in NRDWP works may be adopted for intra village OHSRs keeping in view the importance given by the Government for early completion of intra works in line with main grid works and felt that the same should be altered.

4. The payment break up for Intra Village OHSRs was adopted as per the break up considered for elevated reservoirs in main grid which is as follows:

- a. Payment conditions as per G.O.Rt.No.989, for intra village OHSR: As the offer is a lump sum, the release of intermediate payment will be made at the percentages specified below.

S. No.	Item	Payment Break up (%)
i.	(a) Completion of Excavation for foundation laying of Lean concrete and RCC Footings/raft including staircase.	10%
	(b)Completion of Columns and braces up to Floor slab of container/ tank including staircase.	10%
ii	Completion of Floor slab/ Bottom slab/Vertical walls/ side walls including staircase.	30%
iii	Completion of Roof/ Top slab, Plastering and finishing including staircase.	15%
iv	Completion of Staircase, Erection of inlet, out let, over flow arrangements/ connections, bypass pipes, fixing of specials as per departmental instructions & DI valves and SS railings, Water level indicator, lightning conductor/ arrestor, inside ladder , Painting with three coats of epoxy paint to inner surface of the reservoir including roof dome and 2 coats of weather proof emulsion painting for external surfaces, lettering, and all other miscellaneous works ,etc., as per specifications and testing for water tightness etc., and complete.	25%
v	After commissioning of the structure/scheme	10%

- b. Payment conditions adopted earlier in NRDWP works:

Sl. No.	Item	Payment Break up (%)
i.	Completion of Excavation of foundation for Footings/raft, laying of lean concrete and Footings/raft.	15%
ii	Completion of Column and brace up to base slab of container/tank.	25%
iii	Completion of Floor slab/bottom slab/ done with ring beam, vertical walls/side walls	20%
iv	Completion of Roof/ Top slab, Plastering and finishing.	15%

v	Completion of Staircase, Erection of inlet, out let, over flow arrangements/ connections, bypass pipes, fixing of specials & valves and railings, water level indicator, lightning conductor/ arrestor, and internal ladder, painting and all other miscellaneous works such as valve chambers etc., complete.	15%
vi	After satisfactory hydraulic water tightness test of the structure.	10%

5. The Engineer-in-Chief, RWS&S, Hyderabad has requested the Government to issue the following amendment to G.O.Rt.No.989, PR&RD (RWS.IV) Dept., dt: 08.12.2016 for payment conditions for intra village OHSRs as recommended by the CEs Committee and also to accord permission to extend the modified payment conditions to the works already entrusted as proposed duly issuing amendment to agreement conditions so that contractors can complete the works within the target time.

Sl. No.	Item	Payment Break up (%)
i.	Completion of Excavation of foundation for Footings/ raft, laying of lean concrete and Footings/raft including staircase.	15%
ii	Completion of Column and brace up to base slab of container/tank including staircase.	25%
iii	Completion of Floor slab/bottom slab/ done with ring beam, vertical walls/side walls including staircase.	20%
iv	Completion of Roof/ Top slab, Plastering and finishing including staircase.	15%
v	Completion of Staircase, Erection of inlet, out let, over flow arrangements/ connections, bypass pipes, fixing of specials & valves and railings, water level indicator, lightning conductor/ arrestor, and internal ladder, painting and all other miscellaneous works such as valve chambers etc., complete.	15%
vi	After satisfactory hydraulic water tightness test of the structure.	10%

6. Government after careful examination of the proposal of the Engineer-in-Chief, RWS&S, Hyderabad observed that higher capacities of Over Head Balancing Reservoirs (OHSRs) are in TDWSP project and for completion of staging the payment condition in agreement is provided as 20%, where as in Intra Village works, the capacity of OHSRs is small. Nearly 10,000 number of OHSRs having capacity 10,000 Liters to 20,000 Liters are to be constructed with local contractors who is having limited finance source. Earlier for NRDWP works, 40% payment is included in the agreement for completion of staging. Further, modified orders will improve the finance status to the contractors and help in completion of OHSRs. Therefore, hereby issue the following amendment to the G.O. 1st read above as appended to the Annexure at Sl.No.01 (a) regarding Payment conditions and also accord permission to extend the modified payment conditions to the works already entrusted duly issuing amendment to agreement conditions.

Sl. No	For		Read as	
i.	(a) Completion of Excavation for foundation laying of Lean concrete and RCC Footings/ raft including staircase.	10%	Completion of Excavation of foundation for Footings/ raft, laying of lean concrete and Footings/raft including staircase.	15%
	(b)Completion of Columns and braces up to Floor slab of container/ tank including staircase.	10%	Completion of Column and brace up to base slab of container/tank including staircase.	25%
ii	Completion of Floor slab/ Bottom slab/Vertical walls/ side walls including staircase.	30%	Completion of Floor slab/bottom slab/ done with ring beam, vertical walls/side walls including staircase.	20%
iii	Completion of Roof/ Top slab, Plastering and finishing including staircase.	15%	Completion of Roof/ Top slab, Plastering and finishing including staircase.	15%
iv	Completion of Staircase, Erection of inlet, out let, over flow arrangements/ connections, bypass pipes, fixing of specials as per departmental instructions & DI valves and SS railings, Water level indicator, lightning conductor/ arrestor, inside ladder , Painting with three coats of epoxy paint to inner surface of the reservoir including roof dome and 2 coats of weather proof emulsion painting for external surfaces, lettering, and all other miscellaneous works ,etc., as per specifications and testing for water tightness etc., and complete.	25%	Completion of Staircase, Erection of inlet, out let, over flow arrangements/ connections, bypass pipes, fixing of specials & valves and railings, water level indicator, lightning conductor/ arrestor, and internal ladder, painting and all other miscellaneous works such as valve chambers etc., complete.	15%
v	After commissioning of the structure / scheme.	10%	After satisfactory hydraulic water tightness test of the structure.	10%

7. The Engineer-in-Chief, Rural Water Supply & Sanitation, Hyderabad shall take necessary action accordingly.
8. This order issues with the concurrence of the Finance Department vide their U.O.No.11458/346/A1/EBS.VIII/2017, dt.28.12.2017.
9. A copy of this order is available on the internet and can be accessed at the address <http://www.tsonline.gov.in /www/goir.Telangana.gov.in>.

(BY ORDER AND IN THE NAME OF THE GOVERNOR OF TELANGANA)

**SMITA SABHARWAL
SECRETARY TO GOVERNMENT (RWS) (FAC)**

To
The Engineer-in-Chief, Rural Water Supply & Sanitation, Hyderabad.
The Chief Engineers, TDWSP, Hyderabad.
Copy to
The Accountant General, Telangana, Hyderabad.
The PS to Secretary to C.M.
The PS to Secretary to Government (RWS)(FAC)
The Finance (EBS.VIII) Department.
SF/SCs.

//FORWARDED::BY ORDER//

SECTION OFFICER