

Office of the Engineer-in-Chief (I.W)
I&CAD Dept., Errum Manzil, Hyderabad

Proc. No. ENC/IW/P&M/EE/DEE-2/AEE.5/SoR 2018 19/Vol.II

Dt: 24.07.2018

Sub: Schedule of Rates(SoR) for the year 2018-19 - Building Work items (Part-III) – Corrigendum/Addendum in respect of approved brands in Section Q, Sub-Sections I to VII under Civil Items of SOR 2018-19 – Requested by ENC(NH&Bldgs), R&B Dept.,– For approval - Reg.

- Ref:**
- 1) G.O.Ms.No.49,I&CAD (PW:Reforms)Dept., dt:2.3.2009
 - 2) ENC (PH) Lr.No. 146/AE4/T2/SoR 2018-19/2015 dt. 05.06.2018
 - 3) ENC (SR & CRN) R&B Dept Lr.No. 5040/EE(R)/DEE1/AEE4/2017 dt. 14.05.2018
 - 4) ENC(NH & Bldgs) R&B Dept Lr. No. DEEII/AE10/SoR 2018-19 Dt:08.06.2018
 - 5) Industrial Consumer Price Index points obtained from Commissioner, Labour Department
 - 6) Minutes of Board of Chief Engineers (BOCEs) meeting on finalization of Schedule of Rates 2018-19 held on 29.05.2018.
 - 7) ENC(NH & Bldgs) R&B Dept Lr. No. DEEII/AE10/SoR 2018-19 Dt:27.06.2018
 - 8) ENC(IW) & Chairman, BOCEs Proc No ENC/IW/P&M/EE/DEE-2/AEE.5/SoR 2018 19/VolI, dated 19.06.2018.
 - 9) ENC(NH & Bldgs) R&B Dept Lr. No. DEEII/AE10/SoR 2018-19 Dt:11.07.2018

In the circumstances as furnished by the Engineer-in-Chief (NH & Buildings), R&B Dept., vide letter 9th cited in the subject matter, the **Addendum** for SoR (Buildings & Electrical) under Section-Q, Sub-sections I to VII in respect of approved Brands/Manufacturers/ Supplier is approved as below.

S No	Section	Names of the Approved Brand/Manufacturer/Supplier
1	Sub Section	PLASTICISERS
	TBSC-Qi-01	BONDIT SUPERPLAST S3 100-300ML/50KG BAG CEMENT
	TBSC-Qi-02	BONDIT SUPERPLAST PL 100-150ML/50KG BAG CEMENT

	TBSC-Qi-03	BONDIT SUPERPLAST S1 500ML/50KG BAG CEMENT
	TBSC-Qi-04	BONDIT SUPERPLAST S1 500ML/50KG BAG CEMENT
	TBSC-Qi-05	BONDIT RTPL 250ML/50KG BAG CEMENT
	TBSC-Qi-06	BONDIT SPEED ACPL 1KG/50KG BAG CEMENT
2	Sub Section	WATER PROOFING COMPUND
	TBSC-Qii-01	BONDIT PROOF IWP 1 100ML/50KG BAG CEMENT
	TBSC-Qii-02	BONDIT AQUA GUARD 2K(12-14m2 IN TWO COATS) TO ACHIEVE 1MM THICKNESS
	TBSC-Qii-03	BONDIT AQUA GUARD 2K(12-14m2 IN TWO COATS) TO ACHIEVE 1MM THICKNESS
	TBSC-Qii-04	BONDIT SBR
	TBSC-Qii-09	BONDIT REPAIR SBR 8L/50KG BAG CEMENT
	TBSC-Qii-10	BONDIT PU GUARD
	TBSC-Qii-11	BONDIT PROOF IWP 1 125ML/50KG BAG CEMENT
3	Sub Section	BONDING AGENTS/ADHESIVES
	TBSC-Qiii-03	BONDIT EPOXY BOND 35-40SFT/KG
	TBSC-Qiii-05	BONDIT TILE ADHESIVE 3KG/SQMT@ 3MM THICK
4	Sub Section	ANTI CORROSIVE AGENTS
	TBSC-Qiv-02	BONDIT RUST REMOVER 40SFT/LTR
	TBSC-Qiv-03	BONDIT COAT ZR 4SQMT/LTR
5	Sub Section	GROUTS
	TBSC-Qv-01	BONDIT ANCHOR SET (YIELD 0.5LTRS/1KG PACK)
	TBSC-Qv-02	BONDIT GROUT 700 (YIELD 2100KG/CUM)
	TBSC-Qv-03	BONDIT GROUT EP1 (YIELD 1.07KG/LTR)
	TBSC-Qv-04	BONDIT GROUT EP2 (YIELD 1.6KG/LTR)

6	Sub Section	MISCELLANEOUS CHEMICALS
	TBSC-Qvi-01	BONDIT SHUTTER OIL (1 LTR COVERS 200 SFT)
	TBSC-Qvi-03	BONDIT HARD TOP (7 KG/SQMT)OVER GREEN CONCRETE FOR LIGHT TRAFFIC
	TBSC-Qvi-09	BONDIT TUFF SEAL, Poly Sulphide Sealant
	TBSC-Qvi-11	BONDIT PLUG 10S
	TBSC-Qvi-12	BONDIT TACCOAT (3-4 SQMT/KG)
	TBSC-Qvi-14	BONDIT CURE WB (4 SQMT/KG) BONDIT COAT 109 (Food grade epoxy)
7	Sub Section	REPAIRING AND TREATMENT WORKS
	TBSC-Qvii-04	BONDIT AQUA GUARD 2K(12-14m2 IN TWO COATS) TO ACHIEVE 1MM THICKNESS

Therefore, all the members of Board of Chief Engineers are requested to note the above addendum and to take necessary action in the matter. accordingly.

Sd/- B. Nagendra Rao; Dt 24.07.2018
Engineer-in-Chief(I.W)
Irrigation & CAD Department and
Chairman, Board of Chief Engineers

- I. Copy Communicated to all the members of Board of Chief Engineers for information and necessary action.
- II. Copy Communicated to the following Heads of Departments for information and necessary action.
 1. Engineer-in-Chief (NH & Buildings), Roads & Buildings Department.
 2. Engineer-in-Chief (SR & CRN), Roads & Buildings Department
 - ✓ 3. Engineer-in-Chief (P.H.), PH & ME Department.
 4. Engineer-in-Chief (P.R.), Panchayat Raj Department.
 5. Engineer-in-Chief (RWS) R W S & S, Department.

Copy to the Superintending Engineer, Irrigation Circle, Irrigation & CAD Department, Red Hill, Hyderabad for necessary action.

Sd/- B. Nagendra Rao; Dt 24.07.2018
Engineer-in-Chief(I.W)
Irrigation & CAD Department and
Chairman, Board of Chief Engineers


for Engineer-in-Chief(I.W) 24/7