


Office of the Engineer-in-Chief (I.W)
I&CAD Dept., Errum Manzil, Hyderabad



Proc. No. ENC/IW/P&M/EE/DEE-2/AEE.5/SoR 2018 19/Vol.II

Dt: 24.07.2018

Sub: Schedule of Rates(SoR) for the year 2018-19 - Building Work items (Part-III) – Corrigendum/Addendum in respect of approved brands in Section Q, Sub-Sections I to VII under Civil Items of SOR 2018-19 – Requested by ENC(NH&Bldgs), R&B Dept.,– For approval - Reg.

- Ref:
- 1) G.O.Ms.No.49,I&CAD (PW:Reforms)Dept., dt:2.3.2009
 - 2) ENC (PH) Lr.No. 146/AE4/T2/SoR 2018-19/2015 dt. 05.06.2018
 - 3) ENC (SR & CRN) R&B Dept Lr.No. 5040/EE(R)/DEE1/AEE4/2017 dt. 14.05.2018
 - 4) ENC(NH & Bldgs) R&B Dept Lr. No. DEEII/AE10/SoR 2018-19 Dt:08.06.2018
 - 5) Industrial Consumer Price Index points obtained from Commissioner, Labour Department
 - 6) Minutes of Board of Chief Engineers (BOCEs) meeting on finalization of Schedule of Rates 2018-19 held on 29.05.2018.
 - 7) ENC(NH & Bldgs) R&B Dept Lr. No. DEEII/AE10/SoR 2018-19 Dt:27.06.2018
 - 8) ENC(IW) & Chairman, BOCEs Proc No ENC/IW/P&M/EE/DEE-2/AEE.5/SoR 2018 19/VolI, dated 19.06.2018.
 - 9) ENC(NH & Bldgs) R&B Dept Lr. No. DEEII/AE10/SoR 2018-19 Dt:11.07.2018

In the circumstances as furnished by the Engineer-in-Chief (NH & Buildings), R&B Dept., vide letter 9th cited in the subject matter, the **Addendum** for SoR (Buildings & Electrical) under Section-Q, Sub-sections I to VII in respect of approved Brands/Manufacturers/ Supplier is approved as below.

S No	Section	Names of the Approved Brand/Manufacturer/Supplier
1	Sub Section	PLASTICISERS
	TBSC-Qi-01	BONDIT SUPERPLAST S3 100-300ML/50KG BAG CEMENT
	TBSC-Qi-02	BONDIT SUPERPLAST PL 100-150ML/50KG BAG CEMENT

AS

	TBSC-Qi-03	BONDIT SUPERPLAST S1 500ML/50KG BAG CEMENT
	TBSC-Qi-04	BONDIT SUPERPLAST S1 500ML/50KG BAG CEMENT
	TBSC-Qi-05	BONDIT RTPL 250ML/50KG BAG CEMENT
	TBSC-Qi-06	BONDIT SPEED ACPL 1KG/50KG BAG CEMENT
2	Sub Section	WATER PROOFING COMPUND
	TBSC-Qii-01	BONDIT PROOF IWP 1 100ML/50KG BAG CEMENT
	TBSC-Qii-02	BONDIT AQUA GUARD 2K(12-14m2 IN TWO COATS) TO ACHIEVE 1MM THICKNESS
	TBSC-Qii-03	BONDIT AQUA GUARD 2K(12-14m2 IN TWO COATS) TO ACHIEVE 1MM THICKNESS
	TBSC-Qii-04	BONDIT SBR
	TBSC-Qii-09	BONDIT REPAIR SBR 8L/50KG BAG CEMENT
	TBSC-Qii-10	BONDIT PU GUARD
	TBSC-Qii-11	BONDIT PROOF IWP 1 125ML/50KG BAG CEMENT
3	Sub Section	BONDING AGENTS/ADHESIVES
	TBSC-Qiii-03	BONDIT EPOXY BOND 35-40SFT/KG
	TBSC-Qiii-05	BONDIT TILE ADHESIVE 3KG/SQMT@ 3MM THICK
4	Sub Section	ANTI CORROSIVE AGENTS
	TBSC-Qiv-02	BONDIT RUST REMOVER 40SFT/LTR
	TBSC-Qiv-03	BONDIT COAT ZR 4SQMT/LTR
5	Sub Section	GROUTS
	TBSC-Qv-01	BONDIT ANCHOR SET (YIELD 0.5LTRS/1KG PACK)
	TBSC-Qv-02	BONDIT GROUT 700 (YIELD 2100KG/CUM)
	TBSC-Qv-03	BONDIT GROUT EP1 (YIELD 1.07KG/LTR)
	TBSC-Qv-04	BONDIT GROUT EP2 (YIELD 1.6KG/LTR)